设 计 DESIGN	林芳芳 2024.02.23	图纸名称 PART NAME					图号/物料编码 PART NO.	
校 对 CO.BY	吴贻绵	Midea(英国)MDRB521MIC系列 说明书					16131000A49450	
标准化 STANDARD							材料 MATERIAL 80g双胶纸	
业 务 seller	张 婧	图样标记 REL	版本号 REV.NO.	重量(g) WEIGHT	比例 scale			
批 准 AUTHORIZE			0		1:1		美的冰箱事业部 MIDEA REFRIGERATION DIVISION	
		共 页 TOTAL SHEETS		第 页 NO. OF SHEETS				

技术要求

1.尺寸: 145*210mm
2.印刷颜色: 单色（灰度印刷）
3.制件必须符合QMB-J036.1008 产品说明书及其它类似印刷件技术规范;
4.除客户特别要求外均参照美的冰箱最新版相关企业标准执行;

标记 MARKER	变更内容	修改日期	签名

Midea

Refrigerator

BOTTOM MOUNTED FREEZER SERIES

USER MANUAL

MDRB521MIC*

SmartHome

Download the app
& activate product

Warning notices: Before using this product, please read this manual carefully and keep it for future reference.
The design and specifications are subject to change without prior notice for product improvement.
Consult with your dealer or manufacturer for details.
The diagram above is just for reference. Please take the appearance of the actual product as the standard.

THANK YOU LETTER

Thank you for choosing Midea! Before using your new Midea product, please read this manual thoroughly to ensure that you know how to operate the features and functions that your new appliance offers in a safe way.

CONTENTS

SPECIFICATIONS

| Product model	MDRB521MIC
Rated Voltage/Frequency	220-240V~/50Hz
Rated Current	1.1A
Total Volume	378L
Fresh Food Storage Compartment Volume	216L
Chill Compartment Volume	40L
Frozen Food Storage Volume	122L
Temperature Rise Time	13h
Freezing Capacity	7.5kg/24h
Overall Dimension (W x D x H)	595x700x2010mm

Smart Home

Wireless Network module model	MWB-S-WB01
Standard	IEEE 802. 11b/g/n
Antenna Type	Printed PCB antenna
Frequency Band	2400-2483.5 MHz
Operating Temperature	0 ℃ ~ 85 ℃ Operation humidity: 10%~85%
Power Input	DC5V/500mA Maximum Transmission power: <20dBm

PRODUCT OVERVIEW

Names of components

1	Door switch	**5**	Fruits & vegetables box
2	LED light	**6**	Meat & fish box
3	Shelf	**7**	Door tray
4	LED light (for some models)	**8**	Drawer

💡 **ATTENTION**

The picture above is only for reference. The actual configuration will depend on the physical product or statement by the distributor.

PRODUCT INSTALLATION

Install Instruction

For refrigerating appliances with climate class

- Depending on the climate class, this refrigerating appliance is intended to be used at ambient temperatures range as specified following table

- The climate class can be found on the rating plate. The product may not operate properly at temperatures outside of the specific range

- You can find the climate class on the product label

Effective temperature range

- The product is designed to operate normally in the temperature range specified by its class rating

| Class | Symbol | Ambient temperature range °C | |
		IEC 62552 (ISO 15502)	ISO 8561
Extended temperate	SN	+ 10 to + 32	+ 10 to + 32
Temperate	N	+ 16 to + 32	+ 16 to + 32
Subtropical	ST	+ 16 to + 38	+ 18 to + 38
Tropical	T	+ 16 to + 43	+ 18 to + 43

### Dimensions and Clearances

- Keep the air circulation free around the cabinet. When installing the unit, ensure 10cm of free space at both sides, 10cm at the top of the unit, and not more than 7.5cm at the rear of the unit.

>100mm

>100mm

>100mm

Required space for air circulation

≤75mm

>100mm

Top View

>100mm

⬤ **ATTENTION**

The picture above is only for reference. The actual configuration will depend on the physical product or statement by the distributor.

Space requirement diagram (when the door is open and when the door is closed)

Width	Overall Height	Depth	Width doors open 125°	Depth doors open 125°
A	B	C	D	E
595	2010	700	920	1168

Notice: All dimensions in mm

Door right-left change

|	List of tools to be provided by the user
	Cross screwdriver
	Putty knife Thin-blade screwdriver
	5/16″ socket spanner
	Masking tape

1. Please power off this appliance before conduct this operation. Remove all food from door shelves.

2. Remove the upper left hinge cover decorative cover, upper right hinge cover and upper right hinge, and disconnect the right signal line (signal line terminal 1, 2) at the top of the box body.

upper hinge cover

upper hinge

decorative cover

2   1

3. Remove the refrigerated door body (be careful not to lose small parts such as the shaft sleeve and stop on the door); Remove the middle hinge and remove the decorative cover of hinge hole on the other side.


middle hinge

decorative cover

4. Remove the freezing door body (be careful not to lose small parts such as the shaft sleeve and stop on the door); Remove the hinge and adjust the angle. Remove and install the lower hinge shaft to the other side of the hinge, and install the modified lower hinge to the other side of the box.

5. Change the refrigerator door:

1) Remove the cover plate of the upper end cover of the refrigeration door and the left decorative cover. Install the upper shaft sleeve and the signal line of the door body to the other side and cover the upper end cover plate. Take out the right decorative cover from the accessory bag and install it to the other side of the upper end cover.

2) Remove the door self-locking, door stop and shaft sleeve of the refrigeration door, take out the left door self-locking from the accessory bag, install it on the left side of the lower end cover of the refrigeration door, change the door stop and shaft sleeve to the left side of the lower end cover of the refrigeration door.

6. Change the freezing door:

1) Remove the shaft sleeve and cap of the upper end cover of the freezing door and install them at the left and right swap positions.

2) Remove the door self-locking, door stop and shaft sleeve of the freezing door, take out the left door self-locking from the accessory bag, install it on the left side of the lower end cover of the freezing door, change the door stop and shaft sleeve to the left side of the lower end cover of the freezing door.

7. Install the replaced freezing door on the lower hinge, then install the middle hinge and cover the hinge hole decorative cover.

8. Remove the upper left hinge cover and upper left hinge from the accessory bag. Place the refrigerated door body on the middle hinge and install the upper left hinge. Connect the refrigerator top signal line 4 to the door body signal line 1, and connect the signal line 2 to the signal line 3. Finally, replace the hinge decorative cover to the right side of the box body (note: when replacing the hinge decorative cover to the right side of the box body, the two inserts on the hinge decorative cover (as shown in the figure) shall be cut off.)

All illustrations without guarantee. Technical changes reserved.

Leveling feet

To avoid vibration, the unit must be leveled.

If required, adjust the leveling screws to compensate for the uneven floor.

The front should be slightly higher than the rear to aid in door closing.

Leveling screws can be turned easily by tipping the cabinet slightly.

Turn the leveling screws counterclockwise to raise the unit, clockwise to lower it.

Moving the appliance

1. Remove all food from inside the appliance.
2. Pull the power plug out, insert and fix it into the power plug hook at the rear or on top of the appliance.
3. Tape parts such as shelves and the door handle to prevent from falling off while moving the appliance.
4. Move the appliance with more than two people carefully. When transporting the appliance over a long distance, keep the appliance upright.
5. After installing the appliance, connect the power plug into a socket out to switch on the appliance.

💡 **ATTENTION**

Precautions before operation:
Before making changes the refrigerator must be disconnected from power.
Precautions should be taken to prevent any personal injury.

Changing the light

• Any replacement or maintenance of the LED lamps is intended to be made by the manufacturer, its service agent or similar qualified person.

💡 **ATTENTION**

This product contains a light source of energy efficiency class (G).

Connecting the appliance

After installing the appliance, connect the power plug into a socket outlet.

💡 **ATTENTION**

After connecting the power supply cord (or plug) to the outlet, wait 2 or 3 hours before you put food into the appliance. If you add food before the appliance has cooled completely, your food may spoil.

Tips for energy saving

- Do not place the appliance near cookers, radiators or other heat sources. If the ambient temperature is high, the compressor will run more frequently and for longer, resulting in increased energy consumption.

- Ensure that there is sufficient ventilation at the base of the appliance, on the sides of the appliance and at the back of the appliance. Never cover ventilation openings.

- Please also observe the spacing dimensions in the chapter "Installation".

- The arrangement of drawers, shelves and racks as shown in the illustration offers the most efficient use of energy and should therefore be retained as far as possible. All drawers and shelves should remain in the appliance to keep the temperature stable and save energy.

- To obtain a larger storage space (e.g. for large refrigerated/frozen goods), the middle drawers can be removed. The top and bottom drawers and shelves should be removed last if necessary.

- An evenly filled refrigerator/freezer compartment contributes to optimal energy use. Therefore, avoid empty or half-empty compartments.

- Allow warm food to cool before placing it in the refrigerator/freezer. Food that has already cooled down increases energy efficiency.

- Allow frozen food to defrost in the refrigerator. The coldness of the frozen food reduces the energy consumption in the refrigerator compartment and thus increases the energy efficiency.

- Open the door only as briefly as necessary to minimise cold loss. Opening the door briefly and closing it properly reduces energy consumption.

- The door seals of your appliance must be perfectly intact so that the doors close properly and energy consumption is not increased unnecessarily.

OPERATION INSTRUCTIONS

Control panel

	Display		Button
1	Refrigerating chamber temperature display area	A	Temperature setting button of refrigerating chamber
2	Freezing chamber temperature display area	B	Temperature setting button of freezing chamber
3	Quick cool icon	C	Super cool/super freezing button
4	Quick freeze icon		
5	Vacation icon		
6	Lock icon		

⦿ ATTENTION

The actual control panel may differ from model to model.

Display

• The first time the power was turn on for the refrigerator, the display screen will total display for 3 seconds. Then the screen enters the normal display of the operation.The first time for using the refrigerator, temperatures of refrigerating chamber, temperature and freezing chamber should be set at 5° C/-18 °C respectively.

• When the error occurs, the display panel shows the error code (see next page), during normal running, the display panel shows the set temperature of refrigerating chamber, freezing chamber.

• Under normal circumstances, if there is no any manual operation on refrigerator last for 30 seconds, the control panel will lock itself automatically, and in locked state, the display light ⬚ will go out after 30 seconds.

Lock / unlock

- In the non-locking state, press and hold the button _{Super / Super} _{Cool / Frz.} _{Hold 3sec.- Unlock} for 3 seconds to enter the locked state and the lock buzzer will sound.

- In the locked state, press and hold the button _{Super / Super} _{Cool / Frz.} _{Hold 3sec.- Unlock} for 3 seconds to enter the unlocked state and the unlocking buzzer will sound.

- After 30 seconds of no button operation, it will automatically enter the locked state, and the external display board with amusic buzzer will sound the lock buzzer at the same time.

- The alarm sound release operation can be carried out in the locked state, and all other key operations must be carried out in the unlocked state.

- If the operation is in the locked state, an error buzzer will be displayed.

Temperature setting of refrigerating chamber

- Click the button _{Fridge} _{Hold 3sec.- Vacation} to change the set temperature of refrigerating chamber, each click of temperature adjusting button of the refrigerating chamber, the set temperature will be reduced 1°C.

- The temperature setting range of refrigerating chamber is 2°C ~ 8°C. When the set temperature is 2°C.

- Click the button again, the set temperature of refrigerating chamber will switch to 8°C.

Temperature setting of freezing chamber

- Click the button Freezer to change the set temperature of freezing chamber, each click of temperature adjusting button of the freezing chamber, the set temperature will be reduced 1°C.

- The temperature setting range for freezing chamber is -24 ~ -16°C.

- When the temperature is -24°C, click the button again, the set temperature of freezing chamber will switch to -16°C.

🔵 **ATTENTION**

Recommended setting: refrigerating chamber 4°C, freezing chamber -18°C.

Vacation mode

- Long press the refrigeration temperature adjustment button(3s) to set/cancel the holiday mode.

- When setting the holiday mode, the refrigeration is turned off, the refrigeration temperature display area is extinguished, and the freezing is automatically set to -18°C;

- Adjusting the refrigeration/freezing/super cool and super freezer buttons will exit the holiday mode.

- When exiting the holiday mode, the refrigeration set temperature will automatically return to the set temperature before the holiday mode; the freezing set temperature will automatically return to the set temperature before the holiday mode; enter the normal operation mode.

Super freeze mode

- Super cool and super freezer mode, press the ⬚ button, the setting sequence is: super cool ->super freezer -> cancel.

- When setting/cancelling the super cool mode, the corresponding super cool icon is on/off.

- When setting the super cool mode, the refrigeration is automatically set to 2°C.

- When exiting the super-cool mode, the set temperature of the refrigerating room will automatically return to the set temperature before the quickcooling mode.

- When the super-freezer mode is set, the corresponding superfreezer icon is lit.

- When the super-freezer mode is set, the freezing is automatically set to -24°C.

- When exiting the super-freezer mode, the set temperature of the freezer compartment will automatically return to the set temperature before the superfreezer mode.

- Super cool mode automatically disabled for 6h.

- Super freezer mode automatically disabled for 24h.

💡 **ATTENTION**

The super-freezer function is designed to maintain the nutritional value of the food in the freezer. It can freeze the food in the shortest time. If a large amount of food is frozen at one time, it is recommended that the user turn on the super-freezer function and put the food in. At this time, the freezing speed of the freezer compartment is increased, which can quickly freeze the food, effectively lock the nutrition of the food, and facilitate storage.

Opening warning and alarm control

- If the refrigerator door is open for 120 seconds without closing, the buzzer will alarm until the refrigerator door is closed; any key will cancel the buzzer alarm.

Fault indication

- The following warnings appearing on the display indicate corresponding faults of the refrigerator. Though the refrigerator may still have cold storage function with the following faults, the user shall contact a maintenance specialist for maintenance, so as to ensure optimized operation of the appliance.

Fault code	Fault Description
E1	Temperature sensor failure of refrigerating chamber
E2	Temperature sensor failure of freezing chamber
E3	Temperature sensor failure of meat & fish zone
E5	Freezing defrost sensor detection circuit error
E6	Communication error
E7	Ambient temperature sensor error

Tips on storing food

Freezer compartment

- The freezer is designated for the storage of food frozen at very low temperature, long-term storage of frozen food, and for the production of ice.

- Only use the shelves in the door of the freezer to store frozen food, not for storing hot food designated for freezing.

- Do not put fresh and frozen food next to each other. The frozen food may thaw.

- When freezing fresh food (such as meat, fish or chopped meat), cut them into parts that can be used at the same time.

- Storing frozen food: instructions are usually stated on the packages, which must be followed. If there is no information on the packaging, food should not be stored for longer than three months from the date of purchase.

- When purchasing frozen food, make sure that it was frozen at a suitable temperature and that the packaging is not damaged.

- Frozen food should be kept in suitable packages to retain the quality and should be returned to the freezer compartment as soon as possible.

- If a package of frozen food shows moisture or abnormal bulging, it is probable that it was stored at the wrong temperature and the content is spoiled.

- The storage period for frozen food depends on the room temperature, the thermostat setting, the frequency of opening the door of the freezer, the type of food and the time of transporting the product from the shop to the household. Always follow the instructions printed on the packaging and never exceed the maximum storage time stated on the package.

Cooling compartment

- To reduce moisture and subsequent ice build-up, never put liquid into the refrigerator in unsealed containers. Frost tends to concentrate in the coolest parts of the evaporator. Storing uncovered liquids results in a more frequent need for defrosting.

- Never put warm foods in the refrigerator. These should first cool down at room temperature and then be placed so as to ensure adequate air circulation in the refrigerator.

- Foods or food containers should not touch the back wall of the refrigerator because they could freeze to the wall. Do not keep regularly opening the door of the refrigerator.

- Meat and clean fish (packed in a package or plastic foil) can be placed in the refrigerator, which can be used in 1–2 days.

- Fruit and vegetables without packaging can be placed in the part designated for fresh fruit and vegetables.

💡 **ATTENTION**

The optimal temperature setting of each compartment depends on the ambient temperature. Above optimal temperature is based on the ambient temperature of 25 °C.

Order	Compartments TYPE	Target storage temp. [°C]	Appropriate food
1	Fridge	+2≤x≤ +8	Eggs, cooked food, packaged food, fruits and vegetables, dairy products, cakes, drinks and other foods not suitable for freezing.
2	✳ ✳✳✳ Four-star rating frozen	x≤-18	With freezing capacity, fast freezing speed, caWith freezing capacity, fast freezing speed, can quickly freeze and store food. Suitable for frozen fresh food such as seafood (fish, shrimp, shellfish), freshwater aquatic products and meat products. Recommended for 3 ~ 6 months, the longer the storage time, the worse the taste and nutrition.
3	(✳✳✳) Three-star rating frozen	x≤-18	With freezing capacity. Suitable for frozen fresh food such as seafood (fish, shrimp, shellfish), freshwater aquatic products and meat products. Recommended no more than 3 months.
4	(✳✳) Two-star rating frozen	x≤-12	Only suitable for medium-term storage of already frozen food, e.g. ice cream. Recommended no more than 1 month.
5	(✳) One-star rating frozen	x≤-6	Only suitable for refrigeration, and short-term storage of small quantities of already frozen food. Recommended no more than 1 week.
6	0-star	-6 ≤x≤ 0	Fresh pork, beef, fish, chicken, some packaged processed foods, etc. (Recommended to eat within the same day, preferably no more than 3 days). Partially encapsulated processed foods (non-freezable foods).
7	Chill	-2 ≤x≤ +3	Fresh/ frozen pork, beef, chicken, freshwater aquatic products, etc. (7 days below 0°C and above 0°C is recommended for consumption within that day, preferably no more than 2 days). Seafood less than 0 for 15 days, it is not recommended to store above 0°C.
8	Fresh food	0 ≤x≤ +4	Fresh pork, beef, fish, chicken, cooked food, etc. (Recommended to eat within the same day, preferably no more than 3 days)
9	Wine	+5≤x≤+20	Red wine, white wine, sparkling wine, etc.

💡 **ATTENTION**

please store different foods according to the compartments or target storage temperature of your purchased.

APP SETUP AND OPERATION

Download the SmartHome App

On an app market (Google Play Store, Apple App Store), search for "SmartHome" and find the SmartHome app. Download and install it on your phone. You can also download the app by scanning the QR code below.

Register and log in

Open the SmartHome app, and create a new account to start (you can also register through a third-party account). If you already have an existing account, use the account to log in.

Connect your devices to SmartHome

1. Please make sure your mobile phone is connected to a wireless network. If it is not, go to Settings and enable wireless networks and Bluetooth.
2. Please power on your devices.
3. Open SmartHome App on your phone.
4. If a message of "Smart devices discovered nearby" appears, click to add.

5. If no message appears, select "+" on the page and select your device in the list of nearby devices available. If your device is not listed, please add your device manually by the device category and device model.

6. Connect your device to the wireless network according to instructions on app. If the connection fails, please follow the instructions provided by the app to continue with the operation.

NOTE

1. Make sure your devices are powered on.
2. Keep your mobile phone close enough to your device when you are connecting your device to the network.
3. Connect your mobile phone to the wireless network at home, and make sure you know the password of the wireless network.
4. Check if your wireless router supports 2.4 GHz band and turn it on. If you are not sure whether the router supports 2.4 GHz band, please contact the router manufacturer.
5. The device cannot connect to the wireless network that requires authentication, and it usually appears in public areas such as hotels, restaurants, etc. Please connect to a wireless network that does not require authentication.
6. Turn off the WLAN+ (Android) or WLAN Assistant (iOS) function of your mobile phone when connecting your device to the network.
7. In the case that your device connected to a wireless network before but it needs to reconnect, please click "+" on the app Home page, and add your device again by the device category and model according to the instructions on app.

CLEANING AND MAINTENANCE

Defrosting

- The refrigerator is made based on the air-cooling principle and thus has automatic defrosting function. Frost formed due to change of season or temperature may also be manually removed by disconnection of the appliance from power supply or by wiping with a dry towel.

Cleaning of door tray

- According to the direction arrow in the figure below, use both hands to squeeze the tray, and push it upward, then you can take it out.
- After washing the tray having been taken out, you can adjust its installing height in accordance with your requirement.

Cleaning of glass shelf

- As the innermost part of the refrigerator liner where contacting the shelves has a backstop, you shall raise the shelves upward, then you can be able to take it out.
- Adjust or clean the shelves according to your requirement.

Cleaning the vegetable drawer

1. Remove the contents of the drawer. Hold the handle of the vegetable drawer and pull it out completely until it stops.

2. Lift the vegetable drawer up and remove it by pulling it out.

💡 **ATTENTION**

Soft towels or sponge dipped in water and non-corrosive neutral detergents are suggested for cleaning. The freezer of shall be finally cleaned with clean water and dry cloth. Open the door for natural drying before the power is turned on. Do not use hard brushes, clean steel balls, wire brushes, abrasives, such as toothpastes, organic solvents (such as alcohol, acetone, banana oil, etc.), boiling water, acid or alkaline items clean refrigerator considering that this may damage the fridge surface and interior.

TROUBLESHOOTING

The following simple issues can be handled by the user. Please call the after-sale service department if the issues are not solved.

| Problem	Possible reason
Failed operation	• Check whether the appliance is connected to power or whether the plug is in well contact.
	• Check whether the voltage is too low.
	• Check whether there is a power failure or partial circuits have tripped.
Odor	• Odorous foods shall be tightly wrapped.
	• Check whether there is any rotten food.
	• Clean the inside of the refrigerator.
Long-time operation of the compressor	• Long operation of the refrigerator is normal in summer.
	• when the ambient temperature is high it is not suggestible having too much food in the appliance at the same time.
	• Food shall get cool before being put into the appliance.
	• The doors are opened too frequently.
Light fails to get lit	• Check whether the refrigerator is connected to power supply and whether the illuminating light is damaged.
	• Have the light replaced by a specialist.
Door can not be properly closed	• The door is stuck by food packages too much food is placed.
	• The refrigerator is tiltedr.
Loud noises	• Check whether the floor is level and whether the refrigerator is placed stably.
	• Check whether accessories are placed at proper locations.

Problem	Possible reason
Door seal fails to be tight	• Remove foreign matters on the door seal.
	• Heat the door seal and then cool it for restoration (or blow it with an electrical drier or use a hot towel for heating).
Water pan overflows	• There is too much food in the chamber or food stored contains too much water,resulting in heavy defrosting.
	• The doors are not closed properly, resulting in frosting due to entry of air and increased water due to defrosting.
Hot housing	• Heat dissipation of the built-in condenser via the housing, which is normal. When housing becomes hot due to high ambient temperature, storage of too much food or shutdown of the compressor is shut down, provide sound ventilation to facilitate heat dissipation.
Surface condensation	• Condensation on the exterior surface and door seals of the refrigerator is normal when the ambient humidity is too high. Just wipe the condensate with a clean towel.
Abnormal noise	• Buzz: The compressor may produce buzzes during operation, and the buzzes are loud particularly upon start or stop. This is normal.
	• Creak: Refrigerant flowing inside of the appliance may produce creak, which is normal.

Do you hear these abnormal sounds as below? Usually these sounds are normal.

CLICK: Some electrical parts in the refrigerator, such as electric valve will make this noise when working. This is normal.

HISSS: When the refrigerant flows into the evaporator, it will make this noise. This is normal.


BRRR: The compressor will make this noise when working, and the buzzes are loud particularly upon start or stop. This is normal.

SSSRRR: The fan motor in the No frost refrigerator will make this noise when working. This is normal.

BLUBB: Refrigerant flowing through the pipes in the refrigerator will make this noise. This is normal.

CRACK：Cracking sound or broken ice sound: the overall structure of the refrigerator, air duct frost will be with the thermal expansion and contraction of the expansion sound, these are also normal physical phenomenon.

DOC AND CERTIFICATIONS

Declaration of Conformity

We hereby confirm that the following customer model names and Midea model names match each other respectively.

Brand	Midea Model	Marketing Model	Factory Model
Midea	HD-500RWEN	MDRB521MIC46	CE-BCD385WX-CT
Midea	HD-500RWEN	MDRB521MIC01	CE-BCD385WX-CT

Application of Council Directives

Standards, to which Conformity Is Declared

(EU)2019/2019:2019;(EU)2021/341:2021 ;
(EU)2019/2016:2019;(EU)2021/340:2021
Test Method: EN 62552-1:2020, EN 62552-2:2020,
EN 62552-3:2020; EN 60704-1:2010+A11:2012，
EN 60704-2-14:2013+A11:2015+A1:2019

Manufacturer's Name:	Hefei Hualing Co., Ltd.
Manufacturer's Address:	No.176 JinXiu Road, Hefei Economy & Technology Development Area, 230601, Hefei, Anhui, P.R. China

We, Hefei Hualing Co., Ltd.
hereby declare that the above-mentioned products comply with the above-mentioned currently valid regulations and standards.

SIGNATURE: _David Yung_   Date: January 10, 2024

CE

Midea hereby declares that the appliance with SmartHome functionality meets the essential requirements and other relevant provisions of the Directive 2014/53/EU. A detailed RED Declaration of Conformity can be found online at www.midea. com among the additional documents on the product page for your appliance.

$C\epsilon$

2.4 GHz band:100mW max.
5 GHz band: 100mW max.

APPENDIX

Special for new European standard

The ordered parts in the following table can be acquired from Service provider channel

Ordered part	Provided by	Minimum time required for Provision
Thermostats	Professional maintenance personnel	At least 7 years after the last model is launched on the market
Temperature sensors	Professional maintenance personnel	At least 7 years after the last model is launched on the market
Printed circuit boards	Professional maintenance personnel	At least 7 years after the last model is launched on the market
Light sources	Professional maintenance personnel	At least 7 years after the last model is launched on the market
Door handles	Professional repairers and final users	At least 7 years after the last model is launched on the market
Door hinges	Professional repairers and final users	At least 7 years after the last model is launched on the market
Trays	Professional repairers and final users	At least 7 years after the last model is launched on the market
Baskets	Professional repairers and final users	At least 7 years after the last model is launched on the market
Door gaskets	Professional repairers and final users	At least 10 years after the last model is launched on the market

Dear customer

1. If you want to return or replace the product, please contact the store where you buy.

(Remember to bring the purchase invoice)

2. If your product breaks down which needs to repair, please contact after-sales service provider.

⬤ **ATTENTION**

The model information inthe product database, as well as the model identifier, can be obtained througha weblink scanned by a QR code, if any, on the energy efficiency label of the product.
For more information about the energy efficiency of the appliance, visit https://ec.europa.eu and search using the model name.
The model name can be found on the rating label of the appliance.

Midea

make yourself at home